Schlumberger

Vx Spectra Procedure

Vx Spectra, Hydrostatic Pressure Test Procedure

Schlumberger Private

Owner:	Testing Services
Document Reference:	101437631
Revision:	AJ
Release Date:	14-Nov-2018

Schlumberger-Private

Vx Spectra Hydrostatic Pressure Test Procedure

Table of Contents

1.	Introduction	3
1.1	Scope	3
1.2	·	
1.3	· ·	3
2.	Abbreviations and Definitions	3
3.	References	4
4.	Safety	4
5.	Test Equipment	5
6.	Pressure Test Profile	e
6.1	With isolation blocks	
6.2	Without isolation blocks	7
7.	Additional step for xxBxxx versions	8
8.	APPENDIX – Fill in Sheet for Test of Venturi Section	8
9.	Revision Record Summary	15

Schlumberger

Vx Spectra Hydrostatic Pressure Test Procedure

1. Introduction

1.1 Scope

The purpose of the test is to verify the structural integrity of the venturi assembly which contains all the pressure retaining parts. It applies to the Vx Spectra integrity assemblies.

The venturi assembly is designed and analyzed according to ASME section VIII division 2.

The pressure test shall be witnessed by SLB and also the Third Party if required.

A pressure test record shall be issued for each pressure test and this test shall be included in the Manufacturing Record Book (MRB). Each record shall specify the component(s) tested.

Appendix A and B consist of fill-in forms to be used during the pressure test. The appendix will be attached to the hydrostatic pressure test report as applicable.

1.2 Applicable Standards and Specifications

The specifications in this Hydrostatic Pressure Test Procedure is according to, or more stringent than, the following standards specifications on verification tests except for API 6A.

ASME VIII Rules for construction of pressure vessels

API 6A Specification for Wellhead and Christmas Tree Equipment (Follow most of the guidelines)

2014/68/EU Pressure Equipment Directive

1.3 Design Requirements

Design pressure : 345 bar (5000 psi)

Design temperature : -46°C to +121°C (-51°F to +250 °F)

 P_{TEST} : 517 ± 10 bar (7500 ± 145 psi)

 P_{WORK} : 345 ± 3 bar (5000 ± 44 psi)

2. Abbreviations and Definitions

Vx Spectra Multiphase Flow Meter EUT Equipment under test

QUEST Is a Web-based application used in Schlumberger to collect Quality, Health, Safety, Security

and Environment (QHSE) information, reporting of hazards and, undesired HSE and SPQ

events.

Unit 1 bar observed at the transmitter on the display inside the control room is

Conversion equivalent to 0 psi at the pressure test bay pressure gauge.

Schlumberger

3. References

<u>Title</u>		Document Number
1.	SWI – Integrity Assembly	DMS# 101401980
2.	SWI – Flanges Assembly	DMS# 101401981
3.	SWI – Manufacturing Trolley	DMS# 101535304

4. Safety

Before proceeding with the test activities, all attending personnel shall be briefed of the safety information.

The employee performing the test must be pressure level 2 certified in QUEST.

Safety / Special Guidelines

- Always decrease the pressure back to 0 psi on the gauge (1 bara) before re-tightening.
- All air must be vented and the EUT completely filled with water before applying pressure.
- A clearly visible sign shall be posted to inform of ongoing activities.
- Responsible person shall ensure that only authorized personnel have access to test area.

Schlumberger Private

Vx Spectra Hydrostatic Pressure Test Procedure

5. Test Equipment

The following test equipment is required and must be checked prior to starting the test.

DESCRIPTION	SIZE/RANGE	REMARKS	TEST INSTRUMENT CALIBRATION CERT REF.
Pressurising Unit.	0-527 bar (0-7644 psi)	5k design	NA
Integrity assembly, blind flanges and seal rings assembly	According to 101401980_SWI_ IntegrityAssembly and 101401981_SWI_ FlangesAssembly respectively.	5k design	NA
Fittings, Hoses, Manifold etc. for test purposes:		Range: 0-1800 bar Test equipment for connecting the blind flanges to the Pressurising Unit, Pressure Transmitter and Recorder.	NA
Test medium		Fresh water.	NA
Pressure gauges		Range: 0-23,000 psi Pressure gauges are used only as a reference.	NA
Temperature recorder	Accuracy: ± 1.6 % of calibrated range	Range: 0 -100 °C	To be attached to report
Pressure recorder	Accuracy: ± 0.5 % of full scale range	Range: 0-1600 bar Test Pressure must be inside calibrated range	To be attached to report

6. Pressure Test Profile

The two different test profiles that can be achieved at SWTC pressure test bays dependant of the Vx Spectra meter type, are described as follows in the next two diagrams.

6.1 With isolation blocks




Figure 1 Pressure Test Profile diagram with isolation blocks




Figure 2 Pressure Test Profile table with isolation blocks

Schlumberger-

Vx Spectra Hydrostatic Pressure Test Procedure

6.2 Without isolation blocks



Figure 3 Pressure Test Profile diagram without isolation blocks




Figure 4 Pressure Test Profile table without isolation blocks

Schlumberger

7. Additional step for xxBxxx versions

For the versions of Vx Spectra which have **no** Isolation Blocks the hydrostatic body pressure test has to be followed excluding sections 6 to 16 as per Figure 3 and figure 4. When Vx Spectra versions have Isolation Blocks option available, hydrostatic seat pressure test will be performed for all of the Pacson valves 101360615, which is attached to the Isolation Blocks. Therefore, perform additional Steps 6 to 16 in the appendix and as per Figures 1 and 2 (pressure test profile diagram and table) accordingly.



The Pacson Valve shall only be hydrostatically pressure-tested to the rated working pressure of the Pacson Valve of 345 bar.



Increase the pressure both to 345 or 517 bar step by step and, in each step to increase a maximum of 70 bar each time and, wait for stabilization.

8. APPENDIX - Fill in Sheet for Pressure Test of Integrity Assembly

A test report shall be issued as a record of this Hydrostatic Pressure Tests. The test report shall comprise a pressure test certificate and the sign-off sheets in this Appendix.

The following shall be attached to the test report:

- Pressure recorder graphs duly signed by operator according to procedure.
- Copies of valid Calibration Certificates for all test instrumentation (Pressure and temperature transmitter).

EUT serial number:	
A test with a maximum pressure of:	. bar, was applied to the Vx Meter.
Pressure test duration:	minutes
Operator name (Print Name):	
Operator signature:	
Quality Inspector name (Print Name):	
Quality Inspector signature:	
Date for pressure test:	

Schlumberger-Private

Vx Spectra Hydrostatic Pressure Test Procedure

A. Preceding Control Activities

Before commencing test the following has to be checked.

Step	Description	Check & Verify	Sign
1	Check that valid calibration certificates are available for test instruments.		
	Acceptance: Valid Pressure & Temperature Transmitters, calibration certificates		
	Record the following SN for the test equipment:		
	Pressure Transmitter:		
	Temperature Transmitter:		
2	Make sure that the Barium Source is not installed before starting the pressure test. Ensure that all bolt marking (At isolation blocks, thermowell, detector and source side) that are specified in the integrity/window assembly are present.		
3	Check that all pressure integrity assembly has been completed in accordance to the Instruction-Procedure 101401980.		
4	Check by visual inspection that Test set-up has been completed in accordance to the Instruction-Procedure 101401981 and 101535304.		

Date:	Comments:
Operator:	



B. Result Sheet

The following shall be verified and recorded as described:

	Start the Pressure recorder and record Pressure:		
	Start the Pressure recorder and record Pressure:		
ا اد			
	Start the Temperature recorder and record ambient temperature:		
	ncrease pressure to approx. 35 bar, (35 bar ± 10 bar).		
	et the pressure settle for 5 minutes, then release pressure to 0 bar (1 bara), and aspect for leaks.		
A	Acceptance: No leak.		
	Start Pacson Valve Seat Pressure Cycle:		
12	Close the Pacson Valve (BLOCK 2) for both Isolation Blocks by tightening it to 2Nm minimally to 16Nm maximally using a 6mm hex bit socket with calibrated orque wrench. See Figure 5.		
0	Open the Autoclave Ports for both Isolation Blocks.		
dı	Ensure that the Autoclave Port for both Isolation Blocks have been dried of all water lroplets after the Autoclave Ports are opened.		
	ncrease pressure gradually in steps of approx. 70 bar each until maximum working bressure of the Pacson Valve, \mathbf{P}_{WORK} , is reached (345 bar).		
С	Pressure should be at P _{WORK} 345 bar (345bar ± 8 bar).		
M	Maintain maximum P _{WORK} until pressure is stabilised. Adjust as relevant.		
W	When Pressure is stabilised close pump valve to pressurising unit and maintains		
P	WORK for a total of 5 minutes.		
R	Record Start Time: Record Start Pressure:		
Δ	Acceptance: Pwork ± 3 bar.		
	Check that pressure drop is within limits as specified for a period of 5 minutes.		
R	Record Stop Time: Record Stop Pressure:		
	Acceptance: Pwork ± 3 bar for 5 minutes.		
	Reduce pressure slowly to approximately 0 bar (1 bara). Inspect for leaks, in articular at the Autoclave Port.		
A	Acceptance: No leak.		



Step	Description	Sign
11	Close the Pacson Valve (BLOCK 1) for both Isolation Blocks by tightening it to	
	12Nm minimally to 16Nm maximally using a 6mm hex bit socket with calibrated torque wrench. See Figure 5.	
	Open the Pacson Valve (BLOCK 2) for both Isolation Blocks. See Figure 5.	
	Ensure that the Autoclave Port for both Isolation Blocks have been dried of all water droplets after the Autoclave Ports are opened.	
12	Increase pressure gradually in steps of approx. 70 bar each until maximum working pressure of the Pacson Valve, P _{WORK} , is reached.	
	CAUTION: Pressure should be at Pwork 345 bar (345bar ± 8 bar).	
	Maintain maximum P _{WORK} until pressure is stabilised. Adjust as relevant.	
	When Pressure is stabilised close pump valve to pressurising unit and maintains	
	P _{WORK} for a total of 5 minutes.	
	Record Start Time: Record Start Pressure:	
	Acceptance: Pwork ± 3 bar.	
13	Check that pressure drop is within limits as specified for a period of 5 minutes.	
	Record Stop Time: Record Stop Pressure:	
	Acceptance: Pwork ± 3 bar for 5 minutes.	
14	Reduce pressure slowly to approximately 0 bar (1 bara). Inspect for leaks, in particular at the Autoclave Port.	
	Acceptance: No leak.	
15	End Pacson Valve Seat Pressure Cycle: Pacson Valve Seat Pressure Cycle Passed?	
16	Confirm pressure is at 0 bar (1 bara).	
	Close the Autoclave Ports for both Isolation Blocks by tightening them to 40.6Nm minimally using 5/8" hex socket with calibrated torque wrench.	
	Open the Pacson Valve (BLOCK 1) for both Isolation Blocks. See Figure 5.	
	Open the Pacson Valve (BLOCK 2) for both Isolation Blocks. See Figure 5.	
17	Increase pressure to approx. 35 bar, (35 bar ± 10 bar). Let the pressure settle for 5 minutes, then release pressure to 0 bar (1 bara), and inspect for leaks.	
	Acceptance: No leak.	



Step	Description	Sign
18	Start First Pressure Cycle: Increase pressure gradually in steps of approx. 70 bar each until test pressure is reached.	
	CAUTION: Pressure should be at P _{TEST} 517 bar (517bar ± 10 bar), (refers to Section 5, Test Equipment)	
	Maintain maximum P _{TEST} until pressure is stabilised. Adjust as relevant.	
	When Pressure is stabilised close pump valve to pressurising unit and maintains	
	PTEST for a total of minimum 15 minutes.	
	Record Start Time:	
19	Check that pressure drop is within limits as specified for a period of 15 minutes.	
	Record Stop Time: Record Stop Pressure:	
	Acceptance: PTEST ± 5 bar for 15 minutes.	
20	Reduce slowly pressure to approximately 0 bar (1 bara). Inspect for leaks.	
	Acceptance: No leak.	
21	End First Pressure Cycle: First Pressure Cycle (Step 18 to 20) Passed?	
22	Start Second Pressure Cycle: Increase pressure gradually in steps of approx. 70 bar each until test pressure, PTEST, is reached.	
	CAUTION: Pressure should be at P _{TEST} 517 bar (517bar ± 10 bar), (refers to Section 5, Test Equipment)	
	Maintain maximum P _{TEST} until pressure is stabilised. Adjust as relevant.	
	When Pressure is stabilised close pump valve to pressurising unit and maintains	
	PTEST for a total of minimum 60 minutes.	
	Record Start Time: Record Start Pressure:	
	Acceptance: PTEST ± 10 bar.	

Schlumberge Private

Vx Spectra Hydrostatic Pressure Test Procedure

Step	Description	Sign
23	Check that pressure drop is within limits as specified for a period of 60 minutes.	
	Record Stop Time: Record Stop Pressure:	
	Acceptance: PTEST ± 10 bar for 60 minutes.	
24	Reduce pressure slowly to approximately 0 bar (1 bara). Inspect for leaks.	
	Acceptance: No leak.	
25	End Second Pressure Cycle:	
	Second Pressure Cycle (Step 22 to 24) Passed?	
26	After successful completion of test, reduce pressure to atmospheric, ventilate, drain and dry off all tested equipment. Please read the Caution message here below.	
27	Pressure recording chart to be signed by all attending parties and marked as follows:	
	EUT Serial Number	
	Date of test	
	Ambient temperature [°C]	
	Operator name and signature	
	Quality Inspector name and signature for witness verification	
28	All records shall be signed and attached to the report.	
29	Certifying Authority to sign report.	

/	n		
	0		
Ca	ut	ion	

Ensure that the Vx Spectra inner and outer surfaces are flushed with dry compressed air. This is done to reduce/eliminate the likelihood of rusting or corrosion due to the moisture content leftover after any hydrostatic pressure test.

Date :	 Comments :
Serial number:	
Operator Sign:	
Quality Inspector Sign:	
Third Party Sign:	
Third Party Stamp:	

DMS # 101437631 Revision AJ **Warning**: The revision controlled source of this document is stored in the Document Management System; a paper version of this document is uncontrolled and should be compared by the user with the latest released source document to ensure it is up-to-date.




Figure 5 Location of the Pacson needle valves and autoclave bleed off plug and gland



The two Pacson needles valves and Autoclave bleed off plug and glands should be labelled BLOCK 1, BLOCK 2 and VENT. In the event that the labelling is unavailable, refer to the figure above to determine the position of each block and vent on the Isolation block.

Schlumberger

Vx Spectra Hydrostatic Pressure Test Procedure

9. Revision Record Summary

Table 1: Document revision record summary table

Revision	Date	Remarks	Prepared By	Reviewed By	Approved By
AF	08-Apr-2016	Standardize all pressure units to bar (0 bar=1 bara). Added Quality Inspector check.	Shuqing Huang	Adalberto Fernandez	Alex Vilstrup
AG	20-July- 2016	Added check for bolt markings. Updated timings, updated hold time	Htoo Aung Paing Bo	Adalberto Fernandez	Patrick Wong
АН	17-May- 2018	 Updated PED Directive from 97/EC/23 to 2014/68/EU Update the close of the Pacson Valve by tightening it to 12Nm minimally to maximally 16Nm using a 6mm hex bit socket with calibrated torque wrench. Replace "90° from Autoclave Port/Vent Line" with BLOCK 1 Replace "180° from Autoclave Port/Vent Line" with BLOCK 2 Update the close of the Autoclave Port by tightening them to 40.6Nm minimally using a 5/8" hex socket with calibrated torque wrench. 	Gareth Chin	Shuqing Huang	Alex Vilstrup
AJ	14-Nov- 2018	Update Hydrostatic Pressure Test Acceptance Criteria to +/- 1% of the test pressure when the pressure holding duration is less than 15 mins as per TS POM.	Gareth Chin	Shuqing Huang	Alex Vilstrup